

# ENO Distribution Grid Interconnections Study Timelines and Costs

Step	Duration	Typical Project Size Requiring Step <sup>3</sup>	Cost
Initial Screening Review	1 month	> 15 KVA	N/A
Feasibility Study	1 month	> 300 KVA	Initial Payment \$1,000 <sup>1</sup>
System Impact Study	2 – 3 months	> 1 MVA	Initial Payment \$20,000 <sup>1</sup>
Facilities Study	3 – 6 months	Needed if upgrades are identified in previous studies	TBD based on complexity and scope
MISO DER-Affected Facilities Study	MISO Quarterly Cycle	1 MW injection to Transmission	\$60,000 <sup>2</sup>
Utility Construction	3 – 15 months	Needed if upgrades are identified in previous studies	TBD based on complexity and scope
Witness Test & Signed Interconnection Agreement	1 month	All Projects	

**NOTES:**

<sup>1</sup> Actuals are trued up at completion of study

<sup>2</sup> Shared among all study participants

<sup>3</sup> Projects below these thresholds may require studies depending on their particular circumstances

*As of May 2024*